


Schedule of Accreditation

issued by

United Kingdom Accreditation Service

2 Pine Trees, Chertsey Lane, Staines-upon-Thames, TW18 3HR, UK

 <p>4072</p> <p>Accredited to ISO/IEC 17025:2017</p>	<p>Morgan Sindall Construction and Infrastructure Ltd</p> <p>Issue No: 073 Issue date: 02 June 2026</p>	
	<p>Cooper House Redgrave Close Cross Point Business Park Coventry CV2 2UU</p>	<p>Contact: Mr G Hall Tel: +44(0) 7753 776 470 E-Mail: Gary.Hall@morgansindall.com Website: www.morgansindall.com</p>
<p>Testing performed by the Organisation at the locations specified</p>		

Morgan Sindall Construction and Infrastructure Ltd is accredited to establish temporary site laboratories in accordance with documented in-house procedure: Procedure Lab 001, 'UKAS Laboratory Initial Set Up' for the scope of activities detailed below (Note NCL = No Current Location)

Current locations covered by the scope of accreditation:

Location details	Activity	Location code
<p>Address Morgan Sindall Construction & Infrastructure Ltd Beckton Depot Upgrade Armada Way Beckton London E6 7FB</p> <p>Local contact Mr Steve Gammon Tel: +44 (0)7971 338256 Email: steve.gammon@morgansindall.com</p>	<p>Testing: Aggregates Concrete – Fresh Concrete – Hardened Soil Sampling Soil</p>	Beckton
<p>No Current Locations</p> <p>Local contact Mr G Hall</p>		NCL
<p>Temporary site</p>	<p>Testing: Aggregates Concrete – Fresh Concrete – Hardened Soil Sampling Concrete – Fresh Soil</p>	Identification with *

Site activities performed away from the locations listed above:

Location details	Activity	Location code
<p>All locations suitable for the activities listed</p> <p>Local contact Mr G Hall Tel: +44 (0)7753 776470 Email: Gary.Hall@morgansindall.com</p>	<p>Testing: Concrete – Fresh Sampling Aggregates Concrete - Fresh</p>	Site



Accredited to
ISO/IEC 17025:2017

Schedule of Accreditation
issued by
United Kingdom Accreditation Service
2 Pine Trees, Chertsey Lane, Staines-upon-Thames, TW18 3HR, UK

Morgan Sindall Construction and Infrastructure Ltd
Issue No: 07 Issue date: 02 June 2026

Testing performed by the Organisation at the locations specified

DETAIL OF ACCREDITATION

Materials/Products tested	Type of test/Properties measured/Range of measurement	Standard specifications/ Equipment/Techniques used	Location Code
AGGREGATES	Sampling aggregates - from stockpiles	BS EN 932-1:1997	Site Beckton*
	Sample reduction using a riffle box	BS EN 932-2:1999	Beckton*
	Sample reduction by quartering	BS EN 932-2:1999	Beckton*
	Particle size distribution - sieving method	BS EN 933-1:2012	Beckton*
	Water content	BS EN 1097-5:2008	Beckton*
CONCRETE - fresh	Sampling fresh concrete on site - spot sample - composite sample	BS EN 12350-1: 2019	Site Beckton*
	Slump	BS EN 12350-2: 2019	Site Beckton*
	Flow	BS EN 12350-5: 2019	Site Beckton*
	Slump Flow	BS EN 12350-8: 2019	Site Beckton*
	Making specimens for strength tests	BS EN 12390-2 :2019	Beckton*
	Curing specimen for strength tests	BS EN 12390-2 :2019	Beckton*
	Air content - pressure gauge method	BS EN 12350-7: 2019	NCL
CONCRETE - hardened	Compressive strength of specimens - including curing	BS EN 12390-2: 2019 BS EN 12390-3: 2019 BS EN 12390-1: 2021	Beckton*



4072

Accredited to
ISO/IEC 17025:2017

Schedule of Accreditation
issued by
United Kingdom Accreditation Service
2 Pine Trees, Chertsey Lane, Staines-upon-Thames, TW18 3HR, UK

Morgan Sindall Construction and Infrastructure Ltd
Issue No: 07 Issue date: 02 June 2026

Testing performed by the Organisation at the locations specified

Materials/Products tested	Type of test/Properties measured/Range of measurement	Standard specifications/ Equipment/Techniques used	Location Code
CONCRETE – hardened (cont'd)	Density	BS EN 12390-7: 2019	Beckton*
GROUT	Grout Fluidity test - Cone method	BS EN 445: 2007	NCL
	Grout Bleed Test	Documented In-House Method TP308T (TP308T/1025)	NCL
SOILS for civil engineering purposes	Sampling earthworks materials - from stockpiles - from laid material	Documented In-House Method No SP003	Beckton*
	Dry density/moisture content relationship - vibrating hammer	BS 1377-4:1990	Beckton*
	In-situ density - sand replacement method - large pouring cylinder	BS 1377-9:1990	Beckton*
	In-situ density - core cutter method	BS 1377-9:1990	NCL
	Particle density – gas Jar	BS 1377-2: 2022	NCL
	Dry density/moisture content relationship (4.5 kg rammer)	BS 1377-2: 2022	Beckton*
	Dry density/moisture content relationship - vibrating hammer	BS 1377-2: 2022	Beckton*
GEOTECHNICAL INVESTIGATION and TESTING - Laboratory testing of soil	Water content	BS EN ISO 17892-1: 2014 + A1: 2022	Beckton*
	Particle Size Distribution	BS EN 17892.4: 2016	Beckton*
END			