


# Schedule of Accreditation

issued by

## United Kingdom Accreditation Service

2 Pine Trees, Chertsey Lane, Staines-upon-Thames, TW18 3HR, UK

 <p><b>0640</b></p> <p>Accredited to ISO/IEC 17025:2017</p>	<h3>Forterra Building Products Limited</h3> <p>Issue No: 031      Issue date: 27 July 2021</p>	
	<p>Concrete Services Laboratory Canton Lane Hams Hall Distribution Park Coleshill Birmingham B46 1AQ</p>	<p>Contact: Mr P J Primmer Tel: +44 (0)1675-468042 E-Mail: peter.primmer@hanson.biz</p>
<p><b>Testing performed at the above address only</b></p>		

### DETAIL OF ACCREDITATION

Materials/Products tested	Type of test/Properties measured/Range of measurement	Standard specifications/ Equipment/Techniques used
<p>PRECAST CONCRETE MASONRY UNITS</p>	<p><u>Dimensional Tests</u></p> <p>Dimensions</p>	BS EN 772-16:2011
	<p><u>Mechanical Tests</u></p> <p>Compressive strength - blocks</p>	BS EN 772-1:2011 + A1:2015
	<p>Transverse strength</p>	BS 6073:Part 1:1981 : Appendix C (Withdrawn)
	<p>Routine rapid control test of compressive strength of blocks by manufacturer (fibre board test)</p>	Documented In-House Method SPR 91
	<p><u>Physical Tests</u></p> <p>Drying shrinkage of autoclaved aerated concrete</p>	BS EN 680:2005
	<p>Flatness</p>	BS EN 772-20:2000
	<p>Net and gross dry density</p>	BS EN 772-13:2000
	<p>Moisture content of calcium silicates and autoclaved aerated concrete</p>	BS EN 772-10:1999
	<p>Water absorption</p>	BS EN 772-11:2011
	<p>Total wet &amp; dry movement</p>	BS EN 772-14:2002

END